

② HEN Evolution $(\Delta T)_{\text{pinch}} = 10^\circ$ (from diagram across BB)

Consider the 4 streams, $(\Delta T)_s$ can be found.

Q absorbed or Q released for each stream can be found by adding Q_i + exchanges across the streams.

$$\text{So } (FCP)_1 = \frac{A + C + F}{180 - 40} = \frac{60 + 78 + 142}{140} = 2 \text{ kW}/^\circ\text{C}$$

$$(FCP)_2 = \frac{B + D + E + CV}{150 - 40} = 4 \text{ kW}/^\circ\text{C}$$

$$(FCP)_3 = \frac{HU + A + B + E}{180 - 60} = 3 \text{ kW}/^\circ\text{C}$$

$$(FCP)_4 = \frac{C + D + F}{130 - 30} = 2.6 \text{ kW}/^\circ\text{C}$$

Step 1. Loop: D - FF - AA - BB - D. Heat exchanger with lowest Q is D (= 40 kW)

Remove D. Increase F by $\frac{40}{1}$, decrease A by $\frac{40}{1}$, increase

B by 40.

TAKE ~~180~~

CV	160 kW	E	90 kW
A	20 kW	F	182 kW
B	190 kW	HU	60 kW
C	78 kW		

~~temperatures across exchangers A, B, D, F will change~~

$$T_{AC} = 180 - \frac{20}{2} = 170^{\circ}$$

$$T_{CF} = 170 - \frac{78}{2} = 131^{\circ}$$

$$T_{BA, \text{ent}} = 131 - \frac{182}{2} = 40^{\circ}$$

Temp will be same because we reallocated the heat!!


$$T_{BE} = 180 - \frac{190}{4} = 102.5^{\circ}$$

(\therefore no D)

$$T_{BA} = 90 + \frac{190}{3} = 153.33^{\circ}$$

$$T_{FC} = 30 + \frac{182}{2.6} = 100^{\circ}$$

(\therefore no D)



Temperature violation across BB!!

(hot stream: 180° , cold stream: 153.3°)

To bring back to pinch level ($\approx 10^\circ\text{C}$), reduce


TBA to 140° [step 2]

$$Q_B = (140 - 90) \times 3 = 150 \text{ kW}$$

Use utility path HU - BB - CU

increase HU & CU by $\rightarrow 190 - 150$
 $\text{decrease B by } 40 \text{ kW}$

Resulting HEN:



Now Step 3. Remove CE from loop C-F-F-C


Reduce C to 0. Increase F by 78

$$Q_{FF} = 260 \text{ kW} \quad (Q_C = 78 \text{ kW})$$

$$Q_{FF} = 260 \text{ kW} \quad (Q_F = 182 \text{ kW})$$

Recalculating Temperatures we get,

(only temperatures for streams 1 & 4 change because only they are in the loop)




Finally, consider loop B-E-B.

$Q_{BB} > Q_{EE}$ So Step 4. Remove EE

EE decreased to 0 \Rightarrow decreased by 90 kW

\therefore BB increased by 90 kW

$$Q_{BB, \text{new}} = 180 + 90 = 270 \text{ kW}$$



There are no more loops and no temperature violations.

HEN Evolution is completed and reduced to absolute minimum number of HENs

(Absolute minimum: 4 streams + 2 utilities - 1

= 5 exchangers.

(HU, AA, BB, FF, CU)